
All proposed tree locations are subject to co-ordination with drainage layout and subject to modification depending on the location of underground services and utilities. Drainage engineer to co-ordinate services layout in conjunction with the landscape plan to avoid conflict as much as possible. Allowance to be made at tender stage for the possible requirement for root barriers once the drainage layout is confirmed, CA to be informed immediately once this is available.

Scale: 1:250 @ A0



# PLANTING SCHEDULES

Amelanchier lamarckii

\* Tb and GI maintained at 600mm/1m high

Hebe 'Green Globe'

Trees							
Species	Abb.	Form	Girth (cm)	Height (cm)	Clear stem (cm)	Root	Quantity
Acer campestre	Ac	Standard Extra Heavy	14-16	425-600	175-200	RB	2
Acer campestre 'Streetwise'	AcS	Standard Extra Heavy	14-16	425-600	175-200	RB	3
Betula utils 'Jacquemontii'	BuJ	Multi Stemmed	1	350-400	I	RB	1
Malus sylvestris	Ms	Standard Selected	10-12	300-350	175-200	RB	1
Carpinus betulus	СЬ	Standard Extra Heavy	16-18	min 450	min 200	RB	1
Carpinus betulus 'Frans Fontaine'	CbFF	Standard Extra Heavy	16-18	min 450	min 200	RB	6
Prunus avium	Pa	Standard Extra Heavy	14-16	425-600	175-200	RB	1
prunus cerasifera	Pc	Standard Selected	10-12	300-350	175-200	RB	1
pinus sylvestrus	Ps	Light Standard	6-8	200-250	min 150	В	1


multistem, 3-5 main stems

Rosa canina (S)	Rc	60-80	С	5L	Branched
Phormium tenax 'Purpureum'	PtP	1	С	15L	Triple Crown
Formal Single Species	Native H	edge Planting			
Name	Abb	Height(cm)	Root	Specification	Centre Spacing
Taxus baccata	Tb	30-40	BR (5L)	Bushy	Single row, 50mm centres
Carpinus betulus	Cb	100-125	В	1	Double row, 50cm centres
Note:					

175-200

\* Cb hedge plants to be planted in doubled staggered rows at centres noted above, 40cm between rows.

Ornamental Shrub Planting:						
Name	Abb	Height (cm)	Root	Container	Habit	Density
Sedum telephium ssp. maximum 'Atropurpureum'	StMA	V	С	5L	Bushy	4/m²
Lavandula angustifolia 'Hidcote	Lh	30-40D	С	5L	Bushy	5/m²
Salvia nemorosa 'Caradonna	SnC	V	С	5L	Bushy	6/m²
Stipa tenuissima	St	V	С	5L	Bushy	6/m²
Nepeta racemosa Walker's Low	NrWL	V	С	5L	Bushy	4/m²
Sarcococca confusa	Sc	30-40D	С	5L	Bushy	5/m²
Bergenia cordifolia 'Rosa Zeiten'	BcRZ	V	С	5L	Bushy	6/m²
Anemone x hybrida 'Honorine Jobert'	AhHJ	V	С	3L	Bushy	4/m²
Eryngium x zabelii 'Big Blue'	EBB	V	С	5L	Bushy	6/m²
Ph lomis fruticosa	Pf	V	С	3L	Bushy	4/m²
Euonymus fortunei 'Silver Queen'	EfS Q	30-40D	С	5L	Bushy	5/m <sup>2</sup>
Prunus laurocerasus 'Otto Luyken	PIOL	30-40	С	3L	Bushy	4/m²
Hebe 'Great Orme'	HGO	30-40D	С	5L	Bushy	5/m²
Hebe 'Red Edge'	HRE	30-40D	С	5L	Bushy	5/m²
Hebe 'Green Globe'	HGG	30-40	С	3L	Bushy	4/m²
Sedum telephium 'Purple Emperor'	STPE	V	С	5L	Bushy	5/m²
Agapanthus "Isis	Ai	V	С	5L	Bushy	5/m²
Rudbeckia hirta	Rh	V	С	5L	Bushy	6/m²
Rosmarinus officinalis	Ro	30-40	С	3L	Bushy	5/m²
Cornus Sanguinie	Cs	60-80	С	5L	Branched	3/m²
Bulbs	Abb	Grade				
Allium hollandicum 'Purple Sensation'	AhPS	5 to 6	*Bulbs to be planted 15cm deep & 15 cm apo			



### SOFT LANDSCAPE SPECIFICATION NOTES

in table 1 of BS3882:2015 specification for Topsoil.

NOTE: All soft landscape works to be carried out in accordance with BS4428:1989.

Subsoil should be broken up to relieve compaction and aid drainage prior to topsoiling to the following depths: - For light and non cohesive subsoils: 300mm - For stiff clay and cohesive subsoils: 450mm

Immediately before spreading topsoil, remove stones larger than 50mm.

# Existing site won topsoil to be reused for soft landscape areas if sufficient quantities are available and the topsoil meets the criteria for multipurpose topsoil as defined

If imported topsoil is required it is to be supplied and spread by the main contractor to the approval of the Landscape contractor, in accordance with BS 3882:2015. To be a natural sandy loam, of medium texture, with a pH between 5.5 and 7.8, not more than slightly stony and free of pernicious weeds. Subsoil to be well broken up prior to top-soiling to relieve compaction. Topsoil depths should be: Areas for Ornamental Shrub Planting: minimum 400mm - Areas for cultivated turf: minimum 150mm - Wildflower Meadow: No topsoil to be used - to be cultivated subsoil only.

Weeds to be prevented from seeding or becoming established by applying a suitable herbicide and allowing the correct time to elapse, as directed by the manufacturer. Compacted soil to be broken up to a depth of 100mm, with any stones, grass tufts or rubbish larger than 50mm in any direction to be removed, leaving a regular and even surface. Suitable slow release fertiliser to be supplied and spread @ 50g/m2 to all planted areas.

Topsoiling should be carried out in the driest conditions possible – cultivation to be carried out when the soil is moist, friable and not waterlogged or frozen. Topsoil should not be handled during or after heavy rainfall or when it is wetter than the plastic limit as defined by BS 3882. Planting should not take place in waterlogged conditions or when the ground is frozen.

### SOIL AMELIORANT

Peat-free compost to be spread over ornamental shrub beds @ minimum 50mm depth prior to cultivation.

### All trees within shrub beds to be planted in separate pits in accordance with tree planting detail.

All plant material to comply with BS 3936 Part 1:1992, be obtained from a nursery certified by the HTA and transported to site in accordance with the HTA Plant Handling Guide: 1996. All trees to be planted to the original root collar and secured in place with underground guying system in accordance with tree planting detail. All trees to be fitted with aeration and irrigation system in accordance with tree planting detail.

If the trees are to beplanted outside of the planting season (late October - Late March) then containerised stock to be used in lieu of root ball to the same specification- allowance to be made for this at tender stage if required once construction timetable is known and CA informed immediately.

### PROPOSED ORNAMENTAL SHRUB PLANTING

All shrubs to be positioned as shown on the drawing and to the density and specification noted in the plant schedule. Planting holes to be 150mm wider than the root spread, have the base ground thoroughly broken up before planting and backfilled with peat free compost. All shrubs to be equally spaced throughout the planting areas to the specified density in a staggered arrangement unless otherwise noted in the planting schedule.

WILDFLOWER SEEDING Wildflower mixes to be sown directly into cultivated low fertility subsoil/ topsoil in accordance with manufacturers recommendations at rate of 5g/m2 for wetland mix and 15g/m2 for everyday wildflower mix (see key for species mixture).

Preparation: Cultivate subsoil, apply a suitable herbicide and allow the correct time to elapse, as directed by the manufacturer, and seed the bed. No fertiliser,

compost or mulch are to be applied to the wildflower bed. Cutting first season: Time of first cut - if sown in Autumn cut in March/April, if sown in Spring cut in August - October after flowering. Height of first cut - 70mm. If sown in Autumn it should also be cut in September/October after flowering.

Cutting second season: March/April - cut to 50-70mm then September/October - cut to 50mm after flowering. To be cut twice a year from then on as per above.

### \*NOTE - At time of each cut all arisings to be removed from the bed to maintain reduced soil productivity.

### **GRASSED AREAS**

Seeded areas should be sown in accordance with BS 3969:1998: Recommendations for Turf for general purposes and BS 4428-1989 General Landscape Operations. Height of initial growth: 100mm - Height of first cut: 50mm - Height of growth: The height of growth must not exceed 100mm at any time. Frequency: Cut as and when necessary to a height of 25mm, using a rotary mower and remove all arisings.

Timing: When grass reaches scheduled height of maximum growth and is reasonably dry. Application: At the time of each cut, trim all grass edges round the base of trees, manholes etc and remove arisings. Sweep all adjoining hard areas clear of cuttings Weeding: Keep the sward substantially free of broad leaved weeds by applying a suitable selective herbicide.

Fertilizer: March application: 15:10:10 Spring turf fertilizer at 35g/m2. - September application: 5:10:10 Autumn turf fertilizer at 50g/m2.

### Upon submission of evidence that certain materials, including plant materials, are not available at the time of the landscape contract, the Landscape Contractor may be permitted to substitute other materials and plants in exceptional circumstances during the contract with an agreed adjustment of prices.

All substitutions shall be of nearest equivalent species and variety to the original specified but shall be subject to approval by the Landscape Architect before any change is made. TIMES OF YEAR FOR PLANTING:

Soft landscape works to be carried out during the first possible planting periods following completion of the building and associated engineering works to car park and access roads in accordance with the times of year for planting notes below: - Native and ornamental trees: During dormant winter period - Late October to late March (only if planted in the planting season otherwise containerised stock

Bare root native transplants: During dormant winter period - Late October to April.

- Container grown ornamental and specimen shrubs: At any time if ground and weather conditions are favourable.

75mm depth of 8-35mm ornamental bark mulch (peat-free) to be supplied and spread to all planting areas. Finished mulch level to be installed and maintained at 25mm below any adjacent kerbs or paving surfaces.

# **MAINTENANCE**

All planting areas to be maintained to a high standard by the contractor for 12 months after practical completion, to ensure the landscape scheme is successful, and discourage decline of the area.

# Minimum frequency of maintenance visits:

December / January / February & March - 1no. visit each month - April to November - 2No. visits each month.

- All planting beds to be re-firmed and kept weed free through hand weeding and application of an approved herbicide where appropriate.

### - All litter to be picked and removed from landscape areas. - Mulch to be topped up as required to maintain the specified thickness.

- The condition of all trees is to be regularly checked, with ties and stakes adjusted or replaced as necessary.

- Shrubs to be pruned at appropriate times of year for each species to promote healthy growth and desirable ornamental features.

- Grass lawn area and wildflower meadow areas to be cut and maintained in accordance with specification note above. All arisings to be removed from site.

- Any defects or plant losses occurring during the first 12 months defects period to be replaced at the contractors expense.

Following the initial 12 month establishment period the ongoing landscape management will be the responsibility of an commercial landscape maintenance contractor under a landscape maintenance contract.


All soft landscaping to be subject to a watering regime which is absolutely essential to ensure the continued success of the scheme, particularly during the initial 12 month establishment period. The watering frequency should be as necessary to ensure the continued thriving of all grass, hedges, trees and ornamental planting. During dry periods minimum weekly visits should be made to the site to ensure the soil has not dried out and to action watering if necessary. The soil should be checked for dryness using either a soil moisture sensor or by inserting a spade into the ground to a depth of 300mm to observe the appearance of the soil. If the soil is moist there is no need to water but if it is bone dry then watering procedure should be carried out immediately. Water supply should be from potable mains water or an approved alternative. The full depth of topsoil should be wet without loosening or damaging plants. Any compacted soil should be broken up sufficiently to allow water to reach the rootzone.

**WATERING TREES** 

March - October: 20 litres to be poured into irrigation pipe twice a week (40 litres in total)

Trees to be watered in accordance with BS 8545-2014 Tree - From Nursery to Independence Trees should be watered via the installed irrigation / aeration pipes around the base of the trees stem in accordance with the manufacturer's instructions to ensure the water reaches the roots of the tree. Below is a suggested watering regime but this should be used as a guide only and may require modification in times of drought or flood, dependant on the ground conditions at the time, which should be monitored as above:





LANDSCAPE DESIGNERS Drawing Size A0

4 ST JOHNS NORTH, WAKEFIELD, WF1 3QA. TEL 01924 332056

C - 17.10.2022 Landscape layout updated - trellis and water feature NB AS

included-, drawing layout amended - 07.10.2022 Existing landscape features updated to take into account of Landscape levels remodeling and re specified to be re-seeded with sandy soil meadow mixes 05.10.2022 Plans consolidated and schedules updated NB

wing Title LANDSCAPE PLAN