

# **Welkins Hall**

## **Tree Work Specification**

### **NOTE:**

Tree numbers refer to Southern Housing tree survey schedule and submitted Tree Location Plan. A Tree Location Plan has been provided, photos are available if required.

#### **T9126 - Holm Oak:**

**Proposed Work:** Reduce height by 3-4m and northern spread by 2-3m to shape.

**Reason:** To continue a phased reduction programme due to potential increased risk presented by tear-out at base and historic stem removals.

**Condition notes:** Previously reduced, tear-out at base and historic stem removals.

#### **T9134 - Holm Oak:**

**Proposed Work:** Reduce canopy height and radial spread by 50% (high pollard).

**Reason:** To initiate periodic pollard regime due to past failure and stem decay.

**Condition notes:** Old tear out on main stem at 2m with decay, suppressed canopy structure.

#### **T9137 - Holm Oak:**

**Proposed Work:** Reduce height and radial spread by 3-4m. Clear basal growth.

**Reason:** To contain canopy size to reduce risk of further stem failures.

**Condition notes:** Old tear out from included bark union at 5m, historic limb removal at 3m with included bark down stem & at 2m.

#### **T9138 - Holm Oak:**

**Proposed Work:** Repollard to previous pollard points.

**Reason:** To maintain a periodic pollard regime and tree will be left exposed by reduction of T9137.

**Condition notes:** Previously pollarded with regrowth suppressed by T9137.

#### **T9139 - Elm:**

**Proposed Work:** Fell & poison stump:

**Reason:** Physiological decline/dieback.

**Condition notes:** Ivy smothered, in decline.

#### **T9143 - Elm:**

**Proposed Work:** Fell & poison stump:

**Reason:** Physiological decline/dieback.

**Condition notes:** In decline, reduced vigour, dieback through upper canopy.

#### **T9100 - Beech**

**Proposed Work:** Fell & grind stump:

**Reason:** Included bark at c/b, extensive squirrel damage.

#### **T9101 - Elm**

**Proposed Work:** Remove 2 x lowest branches, clear stem.

**Reason:** Height clearance.

#### **T9103 - Lime**

**Proposed Work:** Crown lift to 2m and reduce side limbs from overhanging adj H Chestnut to provide at least 2m clearance.

**Reason:** Height clearance and to enhance development of tree.

**T9106 - Lime**

**Proposed Work:** Remove 6 x lowest side branches at crown break.

**Reason:** Height clearance and to enhance development of tree.

**T9107 - Elm**

**Proposed Work:** Crown lift to 2m.

**Reason:** Height clearance.

**T9109 - Beech:**

**Proposed Work:** Fell & poison stump:

**Reason:** Extensive squirrel damage.

**T9110 - Elm**

**Proposed Work:** Crown lift to 3m and reduce side limbs from overhanging adj H Chestnut to provide at least 2m clearance.

**Reason:** Height clearance and to enhance development of tree.

**T9111 - Elm**

**Proposed Work:** Crown lift to 3m and reduce side limbs from overhanging adj H Chestnut to provide at least 2m clearance.

**Reason:** Height clearance and to enhance development of tree.

**T9112 - Lime**

**Proposed Work:** Remove basal growth; remove small stem building side; side limbs to roof hgt; rubbing limb at 9m; red. damaged stem by 5m.

**Reason:** To reduce from building and enhance development of tree.

**T9116 - Lime**

**Proposed Work:** Crown lift to 3m, remove side branches growing towards/around camera column/obscuring viewing angle.

**Reason:** To provide height clearance and improve/maintain security camera view.

**T9117 - Privet (Tree)**

**Proposed Work:** Clear building by 1-2m.

**Reason:** To prevent contact with building.

**T9118 - Privet (Tree)**

**Proposed Work:** Clear building by 1-2m.

**Reason:** To prevent contact with building.